TUMKUR DIVISION.

Notice dated 11th August 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 8th September 1928, for Raising the waste weir of Dharmasagara tank Regd. No. 40 of Kortagere Sub-Taluk, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees four hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the waste weir of Dharmasagara tank Regd. No. 40 of Kortagere Sub-Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates and rates less than the lowest will not be accepted.

Approximate quantity for Raising waste weir of Dharmasagara Tank Regd. No. 40 of Kortagere Sub-Taluk.

No.	Items of work	Per	Quantity
1	Jungle clearing	Grade	31
2	Cutting grip and toe trench in old bund	S.yd.	5,115
3	Earthwork to bund gravelly soil watering and tamping, etc. ...	C.yd.	1,738
4	Turfing, sanding, watering, etc.	S.yd.	2,796
5	Rough stone revetment new	C.yd.	227
6	Earthwork excavation	„	10,221
7	Dismantling masonry	C.ft.	169
8	Scraping old mortar plaster and cutting steps for jointing new masonry.	S.ft.	3,882
9	Concrete in surki mortar	C.ft.	2,329
10	Burnt brick in surki mortar	„	6,017
11	Burnt stone slabs 6" dressed	S.ft.	1,259
12	Cutting notches in slabs and providing key stones for both waste weirs.	No.	110
13	Plastering with surki mortar	Sqr.	60·16
14	Cutting bund for revetment	Lump sum	

V. V. PATANKAR,
Executive Engineer.